

Update from the County on Ridgewood Resurfacing: [April 25, 2022](#)

Please note, the work below will result in periodic lane closures on Ridgewood.

Later this week or the first of next week, our contractor (ESTEP Construction) will begin work on Ridgewood making adjustments to drainage structures, constructing swales and adding some curb in select areas.

This work should be completed by the end of May. In early June our Road Operations staff will begin placing asphalt to remove the inverted crown. This operation should take a week and will involve daily closures of the road while asphalt is placed. I would anticipate around the week of June 6th for this effort. This pavement will be left 1-inch short of final design to allow the finish course to be laid by our resurfacing contractor when the balance of Ridgewood is resurfaced. This will provide a more uniform surface with less pavement joints.

Ridgewood is included on the Countywide road resurfacing list. As such, it is difficult to say exactly where this road falls into contractor production. It will likely be late summer or fall. We will follow up once this timeframe becomes more certain.